

No.	Details of work	Per	Quantity
<i>Constructing Right waste weir 355' long at R. L. 50'00.</i>			
1	Earthwork excavating foundation partly gravel and partly soft rock.	C.yd.	888
2	Burnt brick in surki mortar	C.ft.	10580
3	Plastering with do	Sqr.	27'00
4	Stone slabs 6" thick	S.ft.	1067
5	Rough stone work	C.yd.	892
6	Jelly booking to apron	"	281
7	Draft clearing	"	920
<i>Constructing a left waste weir 120' long at R. L. 50'00.</i>			
1	Earthwork excavation in soft rock	C.yd.	220
2	Concrete in surki mortar	C.ft.	473
3	Burnt brick in do	"	1149
4	Plastering in do	Sqr.	8'00
5	Stone slabs 6" thick	S.ft.	585
6	Rough stone work	C.yd.	185
7	Removing and resetting old apron	Lumpsum	
8	Providing shutters to regulator at A	Do	
<i>Improving lifting dam across Kodihalla.</i>			
1	Earthwork excavation	C.yd.	22
2	Burnt brick in surki mortar	C.ft.	1248
3	Plastering in do	Sqr.	2'77
4	Rough stone work, new	C.yd.	108
5	Do using old stone	"	74
6	Clearing slush and removing silt blocking up water way	Lumpsum	
<i>Improving the feeder channel.</i>			
1	Earthwork cutting and forming into bank	C.yd.	4758
2	Rough stone in mortar	C.ft.	188
3	Do work (new)	C.yd.	7
4	Revetting sides of channel at sites of breaches	Lumpsum	
5	Providing two stone work pipe sluices in channels	Do	

B. L. STEINLE.
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification.

The attention of the public is invited to the notice of calling for tenders for constructing a girder bridge across Nallur Halla on Shimoga-Mangalore Road, vide page 1086 and 1087 of the *Mysore Gazette* dated 15th November 1927.

M. A. SRINIVASACHARI.
Executive Engineer.

CHITALDRUG DIVISION.

FORM OF ADVERTISEMENT.

Dated 23rd December 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 31st January 1928, for constructing a Town Building at Harihar, Harihar Sub-Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of the year.

and conditions may be seen at the Executive Engineer's Office.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit
---------------------	--------------	---------------

4. Each tender must be accompanied by a deposit of Rs. 300 in cash as earnest money and be superscribed "Tender for constructing a Town Hall Building at Harihar in Harihar Sub-Taluk.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing a Town Hall at Harihar:—

No.	Items of work	Per	Quantity
1.	Earthwork excavation and filling in basement	C.yd.	129
2.	Filling foundation with concrete	C.ft.	1729
3.	Stone in mortar foundation and basement	"	2063
4.	Burnt brick in mortar	"	4206
5.	Burnt stone slabs 6" thick dressed and fixed	S.ft.	609
6.	Plastering with chunam	Sqr.	83.23
7.	Pointing with cement for basement	"	4.20
8.	White and colour washing	"	83.23
9.	Teakwood wrought and put up with wood oiling	Cft.	116.32
10.	Burnt stone pillars with base and caps, etc.	No.	2
11.	Burnt brick in chunam arch work	C.ft.	82
12.	Teakwood pannelled doors with 3½" x 4½" frames 1½" thick shutters and fittings complete.	S.ft.	210
13.	Teakwood windows with 3½" x 4½" frames 1" thick shutters in two halves each half glazed and half pannelled including ¾" iron bars clamps and fittings, etc., complete.	"	310
14.	Teakwood circular ventilators	"	35.30
15.	Flooring with 1st class Mangalore tiles over 3" concrete and cement pointing.	S.qr.	12.60
16.	Flooring with 1½" to 2" thick Cuddapah slabs over 3" concrete and cement pointing.	"	1.26
17.	Chacolate painting two coats to doors and windows	"	7.56
18.	Wood oiling two coats to doors and windows	"	4.29
19.	Roofing with 1st class Mangalore tiles on teak reepers including plaining.	"	22.94
20.	Ridge tiles set in mortar	R.ft.	128
21.	Teakwood planking to valleys	"	128
22.	Zinc sheets to valley	"	94
23.	Teakwood eave board ornamental to verandah including painting.	"	28
24.	Cornice 9" x 9" around the building	"	214
25.	Teakwood pendants to verandah	No.	4
26.	Masonry finials over gable ends	"	6
27.	Binding walls	R.ft.	124
28.	Tarring to wood work	Lumpsum	
29.	Inscription in front	"	
30.	Levelling ground and clearing site	"	
31.	Ornamentation to front door for side rooms and front windows.	"	
32.	Providing teakwood ventilators	S.ft.	63
33.	Unforeseen items	Lumpsum	

A. TANDONI RAO,
Executive Engineer.